

# Designer Contracts

Method Statement

Sep-22

22

|                               |  |
|-------------------------------|--|
| <b>Method statement title</b> | Bundling, Handling & Laying Gripper<br>Gripper         |
| <b>Description of works</b>   | General-Bundling, Handling & Laying Gripper<br>Gripper |

## Resources

### Personal details ( including estimated employee numbers/trades and working hours)

Designer Contracts Staff  
Sub-Contractor Fitters

### Training Details (including specific training, competency and experience requirementst for both operatives & supervisors)

IOSH Training - All Regional Managers  
Asbestos Awareness Training - All staff who visit site  
Manual Handling Training - All staff  
H & S Training - All Managers and Fitters who visit sites carry CSCS cards  
Site Induction Training & Toolbox Talks - All Fitters

### Sub-Contractor work Element / Personnel (including type of sub-contracted work and workforce size/trades)

Bundling handling and laying carpet gripper.

### Supervisor details and arrangements (including supervisor/operatives ratio, sub-contractor supervision details and arrangements for young persons/apprentices)

Managers to supervise on a regular basis and work closely with Site Management and attend all meetings as required to relay information to their teams.

|  |
|--|
| <b>Plant / Equipment requirement details (including vehicle movement and inspection/maintenances/testing arrangements)</b>   |
| No plant used on site.<br><br>Hammer, nails, screwdriver, screws, staple gun, staples.<br>For concrete floors use relevant adhesive - see COSHH assessment.  |
| <b>Materials, Movement and storage details (including control of manual handling, movement between levels, traffic interface and ignition)</b>   |
| Carpet gripper, tape and box<br><br>Materials will be brought to site by sub contractors with on site movements controlled by site contractors<br>All materials to be delivered to work area and unloaded. All materials will be stacked in accordance with health & safety working practices.<br>All adhesives to be handled with care.<br>Adhesives only to be used in well ventilated areas.  |
| <b>Sequence of work ( including site access, preparation and co-ordination of work)</b>  |
| When bundling/handling gripper always wear safety gloves.<br>Bundle grippers into no more than 10 sticks with pins facing inwards.<br>Tape up bundles neatly.<br>Always handle gripper in a safe manner.<br>Waste gripper should always be bundled or placed in a box, never a bag. <span style="float: right;">To fit, lay gripper approx 5mm away from wall and hammer nails into it to secure. For stairs, staple or screw on the tread. For riser use hammer and nails.</span> |

**Risk Assessment(s) for Significant Risks**

| Are there risk assessments for:                | Yes | No | N/A | Risk Assessment Titles   |
|--|-----|----|-----|--|
| Access / egress                                | X   |    |     | Site Specific Risk Assessment  |
| Place of Work                                  | X   |    |     | Site Specific Risk Assessment  |
| Others at risk (eg public)                     |     |    | X   | Site Specific Risk Assessment  |
| COSHH, noise, vibration, fire etc              | X   |    |     | Relevant COSHH assessments depending on product used - Head Office will provide this |
| Environmental risks (inc asbestos/silica dust) |     | X  |     | Site Specific Risk Assessment  |
| Sub-contracted activities                      | X   |    |     | Site Specific Risk Assessment  |

**Control Measures to be used**

|   | Yes | No | N/a | Control Measure Name |
|---|-----|----|-----|----------------------|
| Permit required   |     |    | X   |                      |
| Security Arrangements   |     |    | X   |                      |
| Special training (confined space, tower erection, use of plant, spills control etc) |     |    | X   |                      |

### Personal Protective Equipment Requirements

|                          | Yes | No | N/a | Control Measure Name   |
|--------------------------|-----|----|-----|--|
| Safety Headgear          | X   |    |     | Hard Hats must be worn by everyone when onsite.                    |
| Safety Footwear          | X   |    |     | Safety footwear is required at all times                           |
| High visibility clothing | X   |    |     | High visibility vest/jacket must be worn at all times.             |
| Safety Gloves            | X   |    |     | Gloves for manual handling and when cutting/spraying adhesive      |
| Hearing protection       |     |    | X   |  |
| Eye protection           |     |    | X   |  |
| Respiratory Protection   |     |    | X   | This activity is below the workplace exposure limit set by the HSE |
| Leg/Knee protection      | X   |    |     | Wear knee pads when kneeling                                       |
| Arm/elbow protection     |     |    | X   |  |
| Fall arrest equipment    |     |    | X   |  |
| Overalls / aprons        |     |    | X   |  |
| Other PPE                |     |    | X   |  |

### Emergency Arrangments

|        | Yes | No | N/A |
|--------|-----|----|-----|
| Rescue | X   |    |     |

#### Details of rescue arrangements

The company will fully comply with all emergency procedures developed by the site.  
Any changes in the emergency procedures and exit routes shall be provided by the site to our Regional Manager in order that such changes can be communicated to the workforce.

|                                | Yes | No | N/A |
|--------------------------------|-----|----|-----|
| Special first aid requirements | X   |    |     |

#### Details of special first aid arrangements

Follow site rules for all first aid requirements and fitters to use site first aid facilities.  
Follow first aid instructions given on relevant COSHH risk assessments

|                             | Yes | No | N/A |
|-----------------------------|-----|----|-----|
| <b>Spillage Containment</b> | X   |    |     |

**Details of spillage containment**

Follow spillage containment instructions given on relevant COSHH assessment.

**Temporary Amended Systems**

|                               | Yes | No | N/a | Comments  |
|-------------------------------|-----|----|-----|---|
| <b>Traffic routes</b>         | X   |    |     | Follow all site signs   |
| <b>Emergency arrangements</b> | X   |    |     | Report any accidents, emergencies or incidents to site office & Designer Contracts Line Manager.<br>Always carry a fully charged mobile phone |
| <b>Services</b>               |     |    | X   |   |
| <b>Other</b>                  |     |    | X   |   |

**Monitoring and Compliance**

|                                 | Yes | No | N/a | Comments |
|---------------------------------|-----|----|-----|----------|
| <b>Monitoring arrangements</b>  |     |    | X   |          |
| <b>Enforcement arrangements</b> |     |    | X   |          |

**General Comments**

We monitor health & safety by using a computerised health & safety management system called BusinessSafe Online which is provided by Peninsula Business Services Limited

The Regional Manager/Senior Contracts Manager visit sites on a regular basis to monitor all aspects of work and health & safety. The health & safety department ensures that all hazards of specific work activities, risk & COSHH assessments are recorded onto BusinessSafe Online which we also use for accident reporting and to indicate what training staff have undertaken and when this needs updating. The health & safety Director is responsible for reviewing reports which have been compiled as a result of monitoring health & safety and the Regional Manager/Regional Assistant Manager are then responsible for ensuring any corrective actions necessary are carried out.