

Designer Contracts

Method Statement

Sep-22

Preliminary Information

Method statement title	Fitting Underlay
Description of works	General Fitting Underlay

Resources

Personal details (including estimated employee numbers/trades and working hours)

Designer Contracts Staff
Sub-Contractor Fitters

Training Details (including specific training, competency and experience requirements for both operatives & supervisors)

IOSH Training - All Regional Managers
Asbestos Awareness Training - All staff who visit site
Manual Handling Training - All staff
H & S Training - All Managers and Fitters who visit sites carry CSCS cards
Site Induction Training & Toolbox Talks - All Fitters

Sub-Contractor work Element / Personnel (including type of sub-contracted work and workforce size/trades)

Handling and laying of underlay

Supervisor details and arrangements (including supervisor/operatives ratio, sub-contractor supervision details and arrangements for young persons/apprentices)

Managers to supervise on a regular basis and work closely with Site Management and attend all meetings as required to relay information to their teams.

Plant / Equipment requirement details (including vehicle movement and inspection/maintenance/testing arrangements)

No plant used on site.

Stanley Knife, sweeping brush and staple gun with staples if wooden floor.
 If concrete floor use adhesive - see COSHH assessment
 Ensure that all portable appliances are portable appliance tested and have the relevant certificate.

Materials, Movement and storage details (including control of manual handling, movement between levels, traffic interface and ignition)

Underlay

Materials will be brought to site by sub contractors with on site movements controlled by site contractors
 All materials to be delivered to work area and unloaded. All materials will be stacked in accordance with health & safety working practices.
 All adhesives to be handled with care.
 Adhesives only to be used in well ventilated areas.

Sequence of work (including site access, preparation and co-ordination of work)

Check condition of ground surface i.e. wet ground
 Check ground surface for obstructions before loading/unloading van
 Walk route to ensure there are no obstructions
 Using a 2 man lift, remove load - i.e. underlay from transit van using the correct safe lifting techniques
 Ensure floors are swept and in good condition before rolling out underlay
 Fit and cut underlay to net area for room/staircase
 Staple underlay to wood floors ensuring staples are straight and not proud
 Spray adhesive underlay to concrete floors to avoid movement - refer to relevant COSHH assessment.
 Bag and remove all waste

Risk Assessment(s) for Significant Risks

Are there risk assesments for:	Yes	No	N/A	Risk Assesment Titles
Access / egress	X			Site Specific Risk Assessment
Place of Work	X			Site Specific Risk Assessment
Others at risk (eg public)			X	Site Specific Risk Assessment
COSHH, noise, vibration, fire etc	X			Relevant COSHH assessments depending on product used - Head Office will provide this
Environmental risks (inc asbestos/silica dust)		X		Site Specific Risk Assessment
Sub-contracted activities	X			Site Specific Risk Assessment

Control Measures to be used

	Yes	No	N/a	Control Measure Name
Permit required			X	
Security Arrangements			X	
Special training (confined space, tower erection, use of plant, spills control etc)			X	

Personal Protective Equipment Requirements

Yes	No	N/a	Control Measure Name
-----	----	-----	----------------------

Safety Headgear	X			Hard Hats must be worn by everyone when onsite.
Safety Footwear	X			Safety footwear is required at all times
High visibility clothing	X			High visibility vest/jacket must be worn at all times.
Safety Gloves	X			Gloves for manual handling and when cutting/spraying adhesive
Hearing protection			X	
Eye protection			X	
Respiratory Protection			X	This activity is below the workplace exposure limit
Leg/Knee protection	X			Wear knee pads when kneeling
Arm/elbow protection			X	
Fall arrest equipment			X	
Overalls / aprons			X	
Other PPE			X	

Emergency Arrangements

	Yes	No	N/A
Rescue	X		

Details of rescue arrangements

The company will fully comply with all emergency procedures developed by the site.
Any changes in the emergency procedures and exit routes shall be provided by the site to our Regional Manager in order that such changes can be communicated to the workforce.

	Yes	No	N/A
Special first aid requirements	X		

Details of special first aid arrangements

Follow site rules for all first aid requirements and fitters to use site first aid facilities.
Follow first aid instructions given on relevant COSHH risk assessments

	Yes	No	N/A
Spillage Containment	X		

Details of spillage containment

Follow spillage containment instructions given on relevant COSHH assessment.

Temporary Amended Systems

	Yes	No	N/a	Comments
Traffic routes	X			Follow all site signs
Emergency arrangements	X			Report any accidents, emergencies or incidents to site office & Designer Contracts Line Manager. Always carry a fully charged mobile phone
Services			X	
Other			X	

Monitoring and Compliance

	Yes	No	N/a	Comments
Monitoring arrangements			X	
Enforcement arrangements			X	

General Comments

We monitor health & safety by using a computerised health & safety management system called BusinessSafe Online which is provided by Peninsula Business Services Limited

The Regional Manager/Senior Contracts Manager visit sites on a regular basis to monitor all aspects of work and health & safety. The health & safety department ensures that all hazards of specific work activities, risk & COSHH assessments are recorded onto BusinessSafe Online which we also use for accident reporting and to indicate what training staff have undertaken and when this needs updating. The health & safety Director is responsible for reviewing reports which have been compiled as a result of monitoring health & safety and the Regional Manager/Regional Assistant Manager are then responsible for ensuring any corrective actions necessary are carried out.