

# Designer Contracts

## Method Statement

### Preliminary Information

|                               |                                     |
|-------------------------------|-------------------------------------|
| <b>Method statement title</b> | Fitting Solid Wood Flooring         |
| <b>Description of works</b>   | General Fitting Solid Wood Flooring |

### Resources

#### Personal details ( including estimated employee numbers/trades and working hours)

Designer Contracts Staff  
Sub-Contractor Fitters

#### Training Details (including specific training, competency and experience requirements for both operatives & supervisors)

IOSH Training - All Regional Managers  
Asbestos Awareness Training - All staff who visit site  
Manual Handling Training - All staff  
H & S Training - All Managers and Fitters who visit sites carry CSCS cards  
Site Induction Training & Toolbox Talks - All Fitters

#### Sub-Contractor work Element / Personnel (including type of sub-contracted work and workforce size/trades)

Fitting Solid Wood Flooring.

#### Supervisor details and arrangements (including supervisor/operatives ratio, sub-contractor supervision details and arrangements for young persons/apprentices)

Managers to supervise on a regular basis and work closely with Site Management and attend all meetings as required to relay information to there teams.

**Plant / Equipment requirement details (including vehicle movement and inspection/maintenances/testing arrangements)**

plant used on site.  
 Dust Suppression for chapsaw/joiner to be Class M.  
 Handsaw, jigsaw, chapsaw, workbench, block & hammer, architrave cutter pin gun, portable drill, plane knives, hoover, biscuit joiner.  
 Ensure that all portable appliances are portable appliance tested and have the relevant certificate.

**Materials, Movement and storage details (including control of manual handling, movement between levels, traffic interface and ignition)**

Solid Wood, doorbars, screws, raw plugs.  
 Materials will be brought to site by sub contractors with on site movements controlled by site contractors  
 All materials to be delivered to work area and unloaded. All materials will be stacked in accordance with health & safety working practices.  
 All adhesives to be handled with care.  
 Adhesives only to be used in well ventilated areas.

**Sequence of work ( including site access, preparation and co-ordination of work)**

Fitter examines the area to be fitted and ensures that it is clear of obstacles.  
 Materials are taken into plot and stored in a suitable area to acclimatise.  
 Scrape and hoover clean the floor before any floor preparation takes place.  
 Bottom of doors are cut using handsaw, lay underlay in relevant areas.  
 Lay and fit solid wood into positions using a block & hammer.  
 Wood cut to size using jigsaw & workbench outside if possible or well ventilated area using dust extraction.  
 Attach beading to skirting board using pin gun.  
 Cut door bars to size using a jigsaw and plane where necessary and screw into position.  
 Remove all waste from site and return to Designer Contracts warehouse for safe disposal.  
 Remove all tools from site and hoover floor clean. Check the floor before leaving.

**Risk Assessment(s) for Significant Risks**

| Are there risk assessments for:                | Yes | No | N/A | Risk Assessment Titles  |
|--|-----|----|-----|---|
| Access / egress                                | X   |    |     | Site Specific Risk Assessment   |
| Place of Work                                  | X   |    |     | Site Specific Risk Assessment   |
| Others at risk (eg public)                     |     |    | X   | Site Specific Risk Assessment   |
| COSHH, noise, vibration, fire etc              | X   |    |     | Relevant COSHH assessments depending on product used<br>- Head Office will provide this |
| Environmental risks (inc asbestos/silica dust) |     | X  |     | Site Specific Risk Assessment   |
| Sub-contracted activities                      | X   |    |     | Site Specific Risk Assessment   |

**Control Measures to be used**

|   | Yes | No | N/a | Control Measure Name |
|---|-----|----|-----|----------------------|
| Permit required   |     |    | X   |                      |
| Security Arrangements   |     |    | X   |                      |
| Special training (confined space, tower erection, use of plant, spills control etc) |     |    | X   |                      |

## Personal Protective Equipment Requirements

|                          | Yes | No | N/a | Control Measure Name  |
|--------------------------|-----|----|-----|---|
| Safety Headgear          | X   |    |     | Hard Hats must be worn by everyone when onsite.                               |
| Safety Footwear          | X   |    |     | Safety footwear is required at all times                                      |
| High visibility clothing | X   |    |     | High visibility vest/jacket must be worn at all times.                        |
| Safety Gloves            | X   |    |     | cut level 5 for use with knives & chisels                                     |
| Hearing protection       | X   |    |     | when using chopsaw  |
| Eye protection           | X   |    |     | when using powertools   |
| Respiratory Protection   |     |    | X   | This activity is below the workplace exposure limit set by HSE set by the HSF |
| Leg/Knee protection      | X   |    |     | Wear knee pads when kneeling  |
| Arm/elbow protection     |     |    | X   |   |
| Fall arrest equipment    |     |    | X   |   |
| Overalls / aprons        |     |    | X   |   |
| Other PPE                |     |    | X   |   |

## Emergency Arrangements

|        | Yes | No | N/A |
|--------|-----|----|-----|
| Rescue | X   |    |     |

### Details of rescue arrangements

The company will fully comply with all emergency procedures developed by the site. Any changes in the emergency procedures and exit routes shall be provided by the site to our Regional Manager in order that such changes can be communicated to the workforce.

|                                | Yes | No | N/A |
|--------------------------------|-----|----|-----|
| Special first aid requirements | X   |    |     |

### Details of special first aid arrangements

Follow site rules for all first aid requirements and fitters to use site first aid facilities.  
Follow first aid instructions given on relevant COSHH risk assessments

|                             | Yes | No | N/A |
|-----------------------------|-----|----|-----|
| <b>Spillage Containment</b> | X   |    |     |

#### Details of spillage containment

Follow spillage containment instructions given on relevant COSHH assessment.

#### Temporary Amended Systems

|                               | Yes | No | N/a | Comments  |
|-------------------------------|-----|----|-----|---|
| <b>Traffic routes</b>         | X   |    |     | Follow all site signs   |
| <b>Emergency arrangements</b> | X   |    |     | Report any accidents, emergencies or incidents to site office & Designer Contracts Line Manager.<br>Always carry a fully charged mobile phone |
| <b>Services</b>               |     |    | X   |   |
| <b>Other</b>                  |     |    | X   |   |

#### Monitoring and Compliance

|                                 | Yes | No | N/a | Comments                     |
|---------------------------------|-----|----|-----|------------------------------|
| <b>Monitoring arrangements</b>  |     |    | X   | Ongoing monitoring by RM/SCM |
| <b>Enforcement arrangements</b> |     |    | X   |                              |

#### General Comments

We monitor health & safety by using a computerised health & safety management system called BusinessSafe Online which is provided by Peninsula Business Services Limited

The Regional Manager/Senior Contracts Manager visit sites on a regular basis to monitor all aspects of work and health & safety. The health & safety department ensures that all hazards of specific work activities, risk & COSHH assessments are recorded onto BusinessSafe Online which we also use for accident reporting and to indicate what training staff have undertaken and when this needs updating. The health & safety Director is responsible for reviewing reports which have been compiled as a result of monitoring health & safety and the Regional Manager/Senior Contracts Manager are then responsible for ensuring any corrective actions necessary are carried out.